

Republic of the Philippines
City of Canlaon
BIDS AND AWARDS COMMITTEE

Control No.: #1

BID FORM

NAME OF PROJECT: **CONSTRUCTION OF COMFORT ROOM AND URINAL**
Brief Description: Supply and delivery of various construction materials
Location: JBCMHS-Main Campus, Brgy.Panubigan, Canlaon City

BILL OF QUANTITIES

Stock No.	Quantity	Unit of Issue	ITEM DESCRIPTION	Unit Cost	Unit Cost	Total Cost
1.	550	pcs.	CHB,4"X8"X16"	18.50		
2.	69	bags	Portland Cement, Type I, 40 kgs.	287.00		
3.	5	cu. m.	Fine Sand	950.00		
4.	6	cu. m.	Gravel - 3/4"	1,347.33		
5.	3	cu. m.	Gravel - 1"	2,166.00		
6.	6	lgths.	Deformed Bar, (16mmØ x 6m)	590.33		
7.	14	lgths.	Deformed Bar, (12mmØ x 6m)	333.33		
8.	53	lgths.	Deformed Bar, (10mmØ x 6m)	238.33		
9.	6	kgs.	GI Tie Wire, GA 16	102.67		
10.	10	shts.	¼"x4'x8', Ordinary Plywood	547.00		
11.	59	bd. ft.	Rough Lumber (2" x 2" x 8')	55.00		
12.	13	shts.	Corrugated GI Sheet (8'), GA 26	657.00		
13.	4	sht.	GI Plain Sheet, GA 26 x 8'	670.00		
14.	9	lgths.	C-Purlins (2" x 3"), G-16	778.33		
15.	2	lgth.	C-Purlins (1 1/2" x 3"), G-16	750.00		
16.	18	lgths.	Angle Bar (1 1/2" x 1 1/2" x 1/4")	1,218.50		
17.	1	lgth.	Square Tube (2" x 2" x 6m)	743.00		
18.	1	lgth.	Rectangular Tube (2" x 3" x 6m)	930.33		
19.	1	lgth.	Rectangular Tube (2" x 4" x 6m)	1,153.00		
20.	2	lgth.	GI Pipe (3"), Sch. 20	3,624.00		
21.	4	lgths.	Hacksaw Blade, Lenox, 24TPI	82.67		
22.	2	pcs.	Cutting Disc, (4" Ø)	577.67		
23.	7	kgs.	Welding Rod, (E6011)	199.00		
24.	2	gal.	Red lead paint	1,013.50		
25.	2	bottles.	Paint Thinner	780.00		
26.	2	pcs.	Paintbrush, 4"	105.00		

Republic of the Philippines
City of Canlaon
BIDS AND AWARDS COMMITTEE

Control No.: #1

BID FORM

NAME OF PROJECT: **CONSTRUCTION OF COMFORT ROOM AND URINAL**
Brief Description: Supply and delivery of various construction materials
Location: JBCMHS-Main Campus, Brgy.Panubigan, Canlaon City

BILL OF QUANTITIES

Stock No.	Quantity	Unit of Issue	ITEM DESCRIPTION	Unit Cost	Unit Cost	Total Cost
27.	200	pcs.	Tekscrew, (5/16" x 2")	4.00		
28.	5	kgs.	Finishing Nails, (4")	90.00		
29.	5	kgs.	Finishing Nails, (3")	92.50		
30.	3	sets	PVC Door (0.80m x 2.10m) with jamb & hinges	3,200.00		
31.	5	sets	4"x4" loose pin hinges(heavy duty)	250.00		
32.	5	sets	3"x3" loose pin hinges(heavy duty)	180.00		
33.	3	sets	4" Sliding Bar Type Stainless Steel Door Shed Lock	70.00		
34.	3	sets	Door Knob, Kwekset w/ Complete Accessories	1,422.00		
35.	4	sets	Toilet bowl (ordinary,pail flush)	1,420.00		
36.	2	sets	Wall Hung Urinal	3,000.00		
37.	3	sets	Wall Hung Bathroom Sink	1,500.00		
38.	7	shts.	Marine Plywood (3/4" x 4' x 8')	1,913.50		
39.	40	pcs.	6 Holes Angle Bracket 90° (3.8cmx6cm)	55.00		
40.	12	pcs.	4 Holes Plane Bracket (3.8cmx6cm)	50.00		
41.	290	pcs.	16mm Flat Screw	2.00		
42.	8	pcs.	Concrete louvers(12" x 12")	160.00		
43.	6	lgths.	uPVC Sanitary Pipes, S-1000 (4"Ø x 3m)	1,127.00		
44.	6	lgths.	uPVC Sanitary Pipes, S-1000 (2"Ø x 3m)	420.00		
45.	7	pcs.	Sanitary Elbow, S-1000 (2"Ø x 45°)	285.00		
46.	8	pcs.	Sanitary Elbow, S-1000 (4"Ø x 45°)	81.00		
47.	7	pcs.	Sanitary Elbow, S-1000 (2"Ø x 90°)	37.00		

Republic of the Philippines
City of Canlaon
BIDS AND AWARDS COMMITTEE

Control No.: #1

BID FORM

NAME OF PROJECT: CONSTRUCTION OF COMFORT ROOM AND URINAL
Brief Description: Supply and delivery of various construction materials
Location: JBCMHS-Main Campus, Brgy.Panubigan, Canlaon City

BILL OF QUANTITIES

Stock No.	Quantity	Unit of Issue	ITEM DESCRIPTION	Unit Cost	Unit Cost	Total Cost
48.	4	pcs.	Sanitary Elbow, S-1000 (4"Ø x 90°)	107.50		
49.	6	pcs.	uPVC Wye, S-1000 (2"Ø)	53.00		
50.	3	pcs.	uPVC Wye, S-1000 (4"Ø)	194.50		
51.	8	pcs.	PVC P-Trap w/ Clean-Out, S-1000 (2"Ø)	128.00		
52.	2	pcs.	PVC Sanitary tee reducer, S-1000 (2" x 4"Ø)	100.00		
53.	3	pcs.	Stainless Floor Drain (4" x 4")	239.00		
54.	6	pcs.	PVC(blue pipe)½"Ø X 8'	180.00		
55.	10	pcs.	PVC elbow(blue)½"Ø	20.00		
56.	5	pcs.	PVC tee(blue)½"Ø	20.00		
57.	1	pc.	PVC 4-way tee(blue)½"Ø	50.00		
58.	1	pc.	PVC female adaptor(blue)½"Ø	20.00		
59.	4	pcs.	Plastic faucet,½"Ø	120.00		
60.	4	pcs.	Solvent cement(250cc)	120.00		
61.	1	pc.	¾" Teflon,big	50.00		
62.	1	pc	PE Male Adapter, ½"Ø	50.00		
63.	1	pc	PE Female Adapter, ½"Ø	50.00		
64.	1	pc	Koten Safety Breaker (KSB), 15AT, 2-pole, 240V, with plastic cover	1,058.50		
65.	80	mtrs	PDX Wire, (2.0mm2, 2-C (#12))	78.00		
66.	100	pcs.	Plastic Ties, 3.6mmx300mm	12.00		
67.	3	rolls	Electrical Tape, 0.16mm x 19mm x 16 yards, plastic, Armak brand	75.00		
68.	8	pcs.	Junction Box, 4x4", uPVC, Orange color with cover & screws	54.00		

Control No.: #1

BID FORM

NAME OF PROJECT: CONSTRUCTION OF COMFORT ROOM AND URINAL
Brief Description: Supply and delivery of various construction materials
Location: JBCMHS-Main Campus, Brgy.Panubigan, Canlaon City

BILL OF QUANTITIES

Stock No.	Quantity	Unit of Issue	ITEM DESCRIPTION	Unit Cost	Unit Cost	Total Cost
69.	1	pc	Utility box, 2x4", uPVC, orange color	32.00		
70.	2	pcs.	Square Box, 5x5", Upvc, orange color	87.00		
71.	7	pcs.	Surfaced Downlight, Can Type, 4", (E-27) black	350.00		
72.	7	pcs.	Led Lamp, Bulb Type, 9 watts, 220V, Standard base (E-27), PHILIPS	120.50		
73.	4	set	Single Pole, Flush Type	359.50		
			TOTAL			

Brand Model: Delivery Period: Warranty:

After having carefully read & accepted your General Conditions. I/We quote on the item/s price/s noted above.

TOTAL BID PRICE (In Words)

BID SECURITY:

AMOUNT:

Submitted by:

Bidder/Supplier
Date: